LIST OF PLANT MATERIAL

COMMON NAME	BOTANICAL NAME	CALIPER	SIZE	QUANTITY*	NOTES
SCOTCH PINE	PINUS SYLVESTRIS	—	5-6'-0	26	EVERGREEN
WHITE CEDAR	THUJA OCCIDENTALIS	—	4'-5'-0	50	
PAPER BIRCH (CLUMP)	BETULA PAPYRIFERA	1-2"	10-12'-0	6	DECIDUOUS TREES
SUGAR MAPLE	ACER SACCHARUM	2"½	12-14'-0	4	
LOMBARDY POPLAR	POPULUS NIGRA ITALICA	2"-2½"	10-12'-0	40	
WEEPING WILLOW	SALIX BABYLONICA	2"-3"	12-14'	32	
LILAC	SYRINGA VULGARIS	CLUMP	5'-6'	25	DECIDUOUS SHRUBS
MOCK ORANGE	PHILADELPHUS	CLUMP	36"-36"	32	
MUGHO PINE	PINUS MUGHO VARIETY	—	1'-2'	6	EVERGREEN SHRUB

* TO BE COUNTED

NORTH

TRENTVIEW DRIVE

DELETE CEDAR HEDGE TAVE THROUGHOUT

LEGEND

	SCOTCH PINE
	WHITE CEDAR.
	PAPER BIRCH
	MAPLE
	LOMBARDY POPLAR
	WEEPING WILLOW
	LILAC
	MOCK ORANGE.
	MUGHO PINE
	SODDED AREAS

LEGEND

1. NEW PROPOSED 18" HIGH RAIL FENCE 1½" O PIPE TYPICAL. POST IN CONC. 5'-0" o/c INDIVIDUAL OPENINGS TO BE 3'-0" TYPICAL. ALL JOINTS TO BE FITTED TIGHTLY AND FULLY WELDED. ALL WELDS TO BE GROUND SMOOTH PAINTING: 1 COAT R.T. 140 'A' PRIMER 2 COATS EXTERIOR GLOSS ENAMEL BLACK ALL PAINTING TO OWNERS APPROVAL
2. NEW PROPOSED 42" HIGH CHAIN LINK FENCE 9 GAUGE SEE SCHEDULE 'A' INDIVIDUAL OPENINGS TO BE 5'-0" TYPICAL
3. NEW PROPOSED PRECAST CONC. PATIO STONES 2'-0" x 2'-0"

LEATHS LANE

PARKHILL ROAD

LANDSCAPE PLAN M3665-L01

REVISIONS		
DATE	NO.	DESCRIPTION
NOV. 28/69	2.	BLOCK 'E' AND SURROUNDING LAND (LOT 7) ADDED TO DRAWING. 25 UNITS @ 1 EACH OF LILAC, MOCK ORANGE, & MUGHO PINE & 5 ADDED.

ONTARIO HOUSING CORPORATION
FAMILY HOUSING PROJECT
PARKHILL RD. - PETERBOROUGH
CHARLES HUFFMAN LTD. - PETERBOROUGH
GENERAL CONTRACTOR.

WILLIAM LETT — ARCHITECT
45 COLBORNE ST., TORONTO 1. TEL. 366-5682
OH 2

SCALE: 1" = 30'-0" | DATE: OCT. 1/69.
DRAWN: W.P. | PROJECT No. 6902

DRAWING No. 2 OF SEVEN

WILLIAM M. LETT MAN ASSOCIATION OF ONTARIO LAND SURVEYORS MEMBER ARCHITECT